

TABELA ROBÓT ZMIEMNYCH POD WYMIANE GRUNTU TRASY 1

km	powierzchnia [m2]		odległość	objętość [m3]		bilans [m3]	
	wykop	nasyp		wykop	nasyp	wykop	nasyp
0+ 0.00	28.17	0.00		0.00	0.00	0.00	0.00
			49.45				
0+ 49.45	35.54	0.00		855.31	0.00	855.31	0.00
			26.85				
0+ 76.30	20.70	0.00		755.02	0.00	1610.33	0.00
			23.70				
0+ 100.00	35.10	0.00		661.23	0.00	2271.56	0.00
			32.05				
0+ 132.05	23.60	0.00		940.67	0.00	3212.23	0.00
			72.00				
0+ 158.12	28.09	0.00		1860.84	0.00	5073.07	0.00
			SUMA	5073.07	0.00		

sprawdzenie  
-5073.07