

Bocznicza TANNE ZESTAWIENIE ROBÓT ZIEMNYCH

l.p.	kilometracja	Powierzchnia [m ²]		Objętość [m ³]		Objętość narastająco [m ³]	
		Nasyp	Przekop	Nasyp	Przekop	Nasyp	Przekop
1	2	3	4	5	6	7	8
1	0	23	8	0	0	0	0
2	25	11	6	424	183	424	183
3	50	7	11	227	218	651	400
4	75	5	7	149	232	800	632
5	100	4	6	108	165	908	797
6	150	3	5	189	265	1096	1062
7	200	2	3	144	203	1240	1264
8	250	3	1	91	63	1331	1327
9	300	3	1	151	29	1482	1357
10	350	1	2	93	57	1575	1413
11	400	1	2	34	81	1609	1494
12	450	2	1	78	65	1687	1559
13	500	0	2	61	77	1748	1635
14	550	0	2	10	100	1758	1736
15	600	1	1	40	78	1799	1814
16	650	0	2	34	83	1833	1897
17	700	0	4	0	161	1833	2058
18	750	0	5	0	229	1833	2287
19	800	0	6	0	280	1833	2567
20	850	0	5	0	295	1833	2862
21	900	0	5	0	269	1833	3131
22	950	0	7	0	296	1833	3427
23	1000	0	5	0	297	1833	3724
24	1050	0	4	0	234	1833	3958
25	1100	0	2	4	148	1837	4106
26	1150	0	1	13	83	1850	4189
27	1200	1	1	26	54	1876	4243
28	1250	0	1	25	47	1901	4291
29	1300	0	2	8	72	1909	4363
30	1350	0	4	1	136	1910	4499
31	1400	0	7	0	264	1910	4764
32	1450	0	4	0	278	1910	5041
33	1500	0	7	0	282	1910	5323
34	1550	0	4	0	267	1910	5590
35	1600	0	5	0	227	1910	5817
36	1650	0	5	0	272	1910	6089
37	1700	0	11	0	423	1910	6512
38	1750	0	13	0	624	1910	7136
39	1800	0	6	0	490	1910	7626
40	1813	2	0	40	153	1950	7780